


Designing semi-automated terminals

Using dynamic modelling tools




Dr. ir. Yvo Saanen


1. Automated terminal amid their main competitors
2. Design approach (semi-) automated terminal
3. Emulation as tool to ensure software quality
4. Concluding remarks

Automated terminals amid their main competitors







- Density: 1500 TEU / ha
- Terminal capacity: 2000 TEU / m quay
- Operational cost reference number: 1
- Investment cost reference number: 5





Designing a semi-automated container terminal



- § S.M.A.R.T. definition of goals and KPI's
 - Realistic operational scenarios
 - Performance targets
 - Operational costs / investment
- § Static terminal design:
 - Berth capacity
 - Storage capacity
- § Simulation of quay operations
„setting the scenarios“
- § Initial drawings of alternatives
- § Simulation (alternative) terminal operations
„productivity assessment“
 - Equipment selection
 - Dimensioning of „handling system“
 - Defining the logistical concept
 - Defining business logic
- § Simulation of terminal during 6 weeks
- § Terminal cost calculation (investment and operational)
- § Implementation plan







- § Target productivity waterside – capable of handling future demands?
 - Peak loads (twin lift, tandem 40, dual cycling, reefer handling, MTs)
 - How many QCs on one vessel?




- § Peak at the landside, gate + rail?

- § Typical peak scenario: how many out of all QCs are actually in operation?


- § How many stacking cranes to meet this demand, in relation to their specifications:
 - Length of stack module
 - Gantry speed & acceleration
 - Hoist speed and acceleration
 - Design of the waterside interchange zone (“buffering”)
 - Rolling percentage (effective rehandling)
 - Landside operation (remote operation)
 - Safety rules (e.g. access to interchange zones)

- § Which automated transportation system is the most cost efficient?

- § How much waterside equipment to meet demands?
 - Interaction between yard equipment and transportation equipment
 - Sequence during vessel loading
 - Etc.




- § The Twin RMG:
 - 2 similar RMGs on one track
 - Ability to mutually support
- § The cross-over twin RMG:
 - One large, one smaller RMG on 2 tracks
 - Ability to pass, and work on either side
- § The cross-over tri RMG:
 - One large, two smaller RMG on 2 tracks
 - One small RMG for either side
 - Ability to pass, and work on either side



(c) TBA 2007 / Semi-automated terminals / AAPA 2007

Iso performance / cost graphs
quay length = 400m, 4 quay cranes, pooled vehicles



- § Terminal 1:
- § 2.0 M TEU
- § 5% transshipment
- § Dwell time: 9 days
- § Peak productivity (WS/LS): 550/400
- § Configuration: 30 modules, 60 TEU long, 8 wide



- § Terminal 2:
- § 3.5 M TEU
- § 50% transshipment
- § Dwell time: 5 days
- § Peak productivity (WS/LS): 720/400
- § Configuration: 52 modules, 45 TEU long, 10 wide




- § Terminal 3:
- § 4.5 M TEU
- § 45% transshipment
- § Dwell time: 4.5 days
- § Peak productivity (WS/LS): 840/450
- § Configuration: 48 modules, 36 TEU long, 10 wide

- § Terminal 4:
- § 1.8 M TEU
- § 5% transshipment
- § Dwell time: 4 days
- § Peak productivity (WS/LS): 375/300
- § Configuration: 24 modules, 26/52 TEU long, 11/8 wide



Effect of the stacklength

2-8 Corridor - Vgantry = 4,0 m/s - Agantry = 0,3 m/s² - Vtrolley = 1,0 m/s - Atrrolley = 0,3 m/s² - Vhoist = 1,0 m/s - Ahoist = 0,33 m/s² - Scenario 3




Effect of gantry speed


Agantry = 0.3 m/s² - Vtrolley = 1,0 m/s - Atrrolley = 0,3 m/s² - Vhoist = 1,0 m/s - Ahoist = 0,33 m/s²




1 out of 4 blocks with reefers



1 out of 3 blocks with reefers



1 out of 2 blocks with reefers





§


Reefer solution:

- Dependent on reefer share
- Dependent on # reefer mechanics
- Dependent on reefer solution (location in the stack module, access, ASC restrictions)

Traffic density
22 QCs - 88 lift AGVs - correct berthing
 Right side of terminal - average number of vehicles per hour





Truck service time module A257



- § **Berth simulation:**
 - Berth occupancy
 - Quay crane utilization
 - Vessel service times
 - Yard occupation throughout the year
 - Handling peaks waterside & landside

- § **Handling system simulation:**
 - Required numbers of yard cranes & shuttle carriers
 - Optimized yard design
 - Reefer solution
 - Design of interchange zones
 - Effect of breakdown and mitigation strategies
 - Algorithms for dispatching, scheduling and grounding

- § **Other:**
 - Solution (conceptually) for scheduling / dispatching ASCs
 - Solution (conceptually) for scheduling / dispatching ShCs





(c) TBA 2007 / Semi-automated terminals / AAPA 2007

Emulation as a way to ensure software quality and performance





or



 TOS (control system)


 TOS (control system)




Real terminal

Virtual terminal

1. Dynamics
2. Safe and inexpensive trial and error environment
3. Analysis of non-repetitive events
4. See process
5. Quantify and prioritize





Key references:

- § Pusan Newport (Zodiac)
- § MSC Home (SPACE/TRAFIC)
- § APMT Virginia (SPARCS)
- § Eurokai Hamburg (TOP-X)
- § APMT Rotterdam (SPACE/TRAFIC)
- § Euromax (SPARCS / TEAMS)
- § APMT Aarhus (SPARCS)


- **Test** new software:
 - Reducing risk
 - More focus on performance
 - Knowing problems earlier in process
 - Insight for non software experts

, **Tune** your operation:

- Anticipation on problems
- Validation of planning
- Replay of operation
- Running future growth scenarios

f **Train** "control room" operators:

- Operate a virtual terminal
- No "learning" impact to operation
- Get immediate feedback
- Practice on irregular operations



(c) TBA 2007 / Semi-automated terminals / AAPA 2007

Concluding remarks



or



- § With the right approach, and the proper tools, automated terminals can be designed and implemented:
- Without major risk
 - Within time
 - Within budget
 - Delivering the targeted productivity
- § The design will vary from site to site, as many conditions determine the “optimal” design
- § Automated terminals – more than any other type of terminal – require proper planning, with a long term vision on service levels and handling capabilities

**TBA B.V.**

Dr. Yvo Saanen – Managing Director

Vulcanusweg 259

2624 AV DELFT

The Netherlands

Tel. +31 15 3805775

Fax. +31 15 3805763

Web www.tba.nl

E-mail info@tba.nl

