



Planning Ahead for Automated Terminals Presentation to AAPA Facilities Engineering Conference



Dan Johnson, P.E. – November 18, 2009

Agenda:

1. Introduction to TBA
2. Critical Background: History and Continuous Change
3. Planning approach used in Portsmouth for APMT (and elsewhere)
4. Example Focus study: Waterside transport



- Headquartered in Delft (Rotterdam)
- **World's largest dedicated simulation firm**
- 75 engineers working full – time
- 8 out of top 10 Global Terminal Operators are customers.
- Active in more than 25 countries
- Completed over 100 terminal projects
- TBA supports port and terminal operators during all stages from concept to realization and thereafter in operations.

Implementing World's Best Practices



A Proven Approach to Focus on Things That Matter

T|B|A

TBA Stands for



Skilled Experts Engineering Success

T|B|A

Study:

- Simulate capacity, strategy, CAPEX studies, e.g. vessel deployments: **TRAFALQUAR**
- Full-terminal **simulation**, peak shift and multi-day (e.g. handling strategy tests): **TIMESQUARE**

Test, Train, Tune:

- Full system emulation: Simulation plus direct connection to TOS and equipment systems: **CONTROLS**

Operate:

- Optimization modules for real-time control in conventional and automated container facilities: **POSCH**
- Automated transport control software (e.g. AGV system operation): **TEAMS**



Selected portfolio for support of container terminal conceptual design (2003-2009):

DPW:

Antwerp Gateway
London Gateway
Fisherman's Island
Jebel Ali CT 2, CT3 & CT4
Rotterdam World Gateway
Southampton extension

PSA: Voltri Terminal Europe extension

Transnet: Nquga & Durban extensions

Others: (many are secret)

Northport, Malaysia extension

Port of Gothenburg extension

Packer Avenue, Philadelphia

HPH:

ECT barge terminal, Rotterdam
Tercat - Barcelona Muelle Prat
Euromax Rotterdam
Thamesport extension

APMT:

Maasvlakte II terminal
Portsmouth, VA
Algeciras extension
Tanjung Pelepas extension

HHLA:

Burchardkai extension
Tollerort extension




- **Optimization** of existing facilities (layout, TOS, operations):
 - DPWorld Port Botany, West Swanson (2006 - 2008)
 - **HHLA – Container terminal Altenwerder** (2007 – 2008)
 - Durban Container Terminal (2007)
 - DPWorld Caucedo, Chennai, Mumbai (2007 - 2009)
 - **APMT Rotterdam** (2007 – 2008)
 - TSI Vancouver (2008)
 - Ocupa Manzanillo (2008)

- **Performance assessment** of equipment specifications
 - NTB (2004, 2006)
 - **Euromax** (2005)
 - APMT-PTP (2006)

- **TOS Optimization (CONTROLS):**
 - **DPWorld Pusan Newport** (2006)
 - **APMT Portsmouth, Rotterdam, Algeciras** (2006 - 2008)
 - Eurogate Hamburg (2007)
 - MSC Home Terminal (2007 – 2009)
 - **DPWorld Antwerp Gateway** (2008 - 2009)
 - Gothenborg Havn (2009)

- **Delivery Automated Equipment Control Systems (TEAMS)**
 - **CTA** (Hamburg, 2002)
 - **Euromax** (Rotterdam, 2008)
 - **Antwerp Gateway** (2007)



Terminal Automation is...


- Complex
- Expensive
- Time-consuming to implement
- Unique, each time
- Environmentally friendly?
- Leveraged?
- Cost-effective?
- “Inflexible”?

Typical Questions:

- Is it right for my facility? When?
- What mode?
- What are implications for me if a nearby terminal automates?




Growth of Terminal Automation by Type



Ea. type typically requires all items above it at same terminal

% Adoption by Large Container Terminals vs. Time

What is the Relative Popularity of Automated Yard Cranes?



ASC - End
 ASC - End + Side
 C-RMG (Side)
 Bridge Crane
 Strad
 RTG



Cost control



Reduction of labor dependency



Logistic control – centralized control & optimization



Reliability and predictability of operations



Safety



Reduction of environmental impact (noise, light, emission)



Reduction of maintenance

Terminal Simulation HPH - Euromax (2003 → 2009)




Terminal design APMT - Portsmouth (2003 → 2009)




Terminal design DPW - Antwerp (2005 → 2009)




4 sites in Operation:	<u>Automated Yard Crane</u>	<u>Automated Transport</u>
• ECT, Rotterdam	ASC	AGV
• Altenwerder, Hamburg	ASC	AGV
• Patrick, Brisbane	N/A	Automated Strads
• Euromax, Rotterdam	ASC	AGV



Notes: Original Automated Terminal, ONE ASC PER RUN, strads used for valet gate service, low ship productivity.




Notes: Successful but sub-par ship productivity.
ASC + AGV; 2 asc per run, 1 over 4 ASC; second
QC hoist is automated.



Note: sub-par ship productivity, unable to sell second site on concept, low density. However, exceeding design throughput capacity is part of what hurts ship productivity.



8 Sites Operating:	Automated <u>Yard Crane</u>	Manual <u>Transport</u>
• DPW Antwerp	ASC	Strad
• APMT, Virginia	ASC	Strad
• Thamesport, UK	ASC (side & end)	Truck
• Pasir-Panjang, Singapore	Bridge Crane	Truck
• Wan-Hai, Tokyo	C-RMG	Truck
• Evergreen, Kaohsiung	C-RMG	Truck
• DPW – Antwerp	ASC	Strad
• Tobishima, Japan	RTG	Truck



Successful concept: ASC + manual shuttles like APMT VA; Just went live, RMG stacks still under-utilized.



Successful in concept: ASC + manual shuttles RMG stacks still under-utilized, good ship productivity; aggressive financing required a more fully-utilized terminal, APMT now negotiating with VIT to share use. Ship: 40 Moves/hr, ASC gantry speed 300 m/min; 6 QC, 30 ARMG




fairly successful, side and end loading; Navis SPARCS ship planning


Layout and Equipment Selection is just a Small Part of the Work

- Design of terminal
 - Equipment Requirements
 - Layout definition in detail - E.g. reefer facilities, transfer zones
- Design control rules for TOS
 - Automated grounding decisions
 - Automated ASC dispatching rules
 - Control mechanisms and collision control rules for ASCs
- Testing and tuning TOS control rules with Emulation is ongoing






Real terminal



Virtual terminal

- New approaches, equipment, operating logic, site size, etc..
- Obtain non-intuitive results: E.g. Is a buffer required for Automated shuttle
- Board members need convincing argument to spend \$\$\$
- Accurate ROI, OPEX, CAPEX calculations
- Accurate engine hours/emissions estimates
- Decide on waterside transport





Definition of operational scenarios

DESIGN DECISION	QC concept: Conventional		Stack orientation: Parallel							
	Throughput per quay: 2,500 TEU/m quay		Throughput per area: 35,000 TEU/ha		QC productivity: 50 mph (gross) 160,000 lifts/yr		Vessel productivity: 300 mph		DS waiting > 8h: <1%	
TARGETS	Terminal dimension: Quay length 3,200m Apron depth 600m		QC work hrs: 5,000	Filling rate: 85%	Dwell time: 5.3 days	Overall peak: 1.15	ASC capacity: 16 bx/h (WS) 14 bx/h (LS)		T/S = 67% (DS, feeder & barge)	Gate / Rail: 20%/day & 7%/hr 15%/day & 5%/hr
CONSTRAINT/ ASSUMPTION										
RESULTS	QUAY Volume: 8.6 M TEU WS peak load: 1,057 bx/h Throughput: 2,700 TEU/m		YARD No. of modules: 90 Dimension (L x W): 35 x 8 TEU Stack height: 5 Land use: ~66% Throughput: 107,000 TEU/ha		EQUIPMENT No of QCs: 32 No of ASCs: 124		GATE/RAIL LS Peak load: 388			

Definition of operational scenarios



Conceptual layouts
Capacity calculation


Assessment of alternatives under dynamic conditions (simulation)

Sensitivity analysis (simulation)

Design of transition trajectory

Cost analysis (OPEX & CAPEX)

Conceptual layouts
Capacity calculation



Definition of
operational scenarios

Conceptual layouts
Capacity calculation


→ Assessment of
alternatives under
dynamic conditions
(simulation)

Sensitivity analysis
(simulation)

Design of transition
trajectory

Cost analysis
(OPEX & CAPEX)

Assessment of
alternatives under
dynamic conditions
(simulation)



Definition of operational scenarios

Conceptual layouts
Capacity calculation

Assessment of alternatives under dynamic conditions (simulation)

→ Sensitivity analysis (simulation)


Design of transition trajectory

Cost analysis (OPEX & CAPEX)

Sensitivity analysis (simulation)

RF QC Performance - RF handling

Twin Carry ShC - Hoist Speed 60/30 - 25 Reefer Modules - Dedicated Assignment - 18 QCs @ 40 ccph - Gantry Speed @ 4.5 m/s - Gantry Acc. @ 0.3 m/s² - Spreader Acc. @ 0.3 m/s² - Trolley Acc. @ 0.3 m/s² - 408 landside bx/h



Definition of operational scenarios

Conceptual layouts
Capacity calculation


Assessment of alternatives under dynamic conditions (simulation)


Sensitivity analysis (simulation)

➔ Design of transition trajectory

Cost analysis (OPEX & CAPEX)


Design of transition trajectory





Cost analysis
(OPEX & CAPEX)

Cost development
ASC 8 wide + Straddle carriers (1 over 2)





Shuttle Carrier
(ShC)

Cassette AGV
(C-AGV)




Automated
Shuttle
(ALV)


Lift AGV
(AGV_L)




QC productivity - Vehicle Comparison [10 QCs @ 40 ccph, 25 TwinRMG modules, 350 landside bx/h]



RMG Productivity per stack module - Compared to previous vehicle numbers for 40 QC mvs/h
 [6 QCs @ 40 ccph, 25 TwinRMG modules, 350 landside bx/h]



Vehicle Order Duration overview - 18 vehicles
 [6 QCs @ 40 ccph, 25 TwinRMG modules, 350 landside bx/h]





Questions?



For Further Questions:

dan.johnson@tba.nl

510.913.6558 (Oakland, CA)