

AAPA Annual Convention & Expo
November 2-4, 2015
Miami, FL

Pier 3 Upgrade Project

Stanley Ryter, PE, PMP
Engineering Project Manager II
Port of Tacoma



Project Team Members

Pier 3 Project Upgrade



Project Team Members

Owner:	Port of Tacoma
Port Project Manager:	Stanley Ryter, PE, PMP
Engineer of Record:	BergerABAM
Electrical Engineer:	Cross Engineering
General and Marine Contractor:	Orion Marine Group
Electrical Subcontractor:	REP
Earthwork Subcontractor:	Roadway Construction
Construction Cost:	\$15M
Total Project Cost:	\$20M





Future Facility Plan

Pier 3 Project Upgrade

- Redevelop the General Central Peninsula
- Realign Pier 4 with Pier 3
- Simultaneously operate up to ten 100'-gauge container cranes
- Berth 2 ultra large container ships



Design Vessel Requirements

Pier 3 Project Upgrade



- Vessels between 5,000-18,000 TEUs (twenty-foot equivalent units)
- Maximum anticipated draft of 50'
- Vessel width – up to 23 containers



Project Overview

Pier 3 Project Upgrade



- Step 1 in the long-term plan
- Strengthening of pier for increased loads


- All new appurtenances
- Electrical distribution capacity upgrade



Constructed Project Elements

Pier 3 Project Upgrade

- 100 precast pre-stressed piles
- Replacement of waterside crane beam
- Upgrade of the fender system
- Upgrade of bollards



Constructed Project Elements (cont)

Pier 3 Project Upgrade



- Strengthening of landside crane beam and installation of 100'-gauge crane rail



- Additional 36 concrete piles on landside crane beam
- New electrical substation for 13.8kV power

Constructed Project Elements (cont)

Pier 3 Project Upgrade



New crane rail



New bollards

Constructed Project Elements (cont)

Pier 3 Project Upgrade




- Infrastructure for future cold ironing
- Relocation of existing light poles
- Demolition of existing 5kV electrical substation



- Maintenance of service for 4 existing 64'-gauge cranes

Schedule and Budget Pier 3 Project Upgrade

- Substantial completion – October 27, 2014
- 460 calendar days construction
- On budget with total project cost of \$20M



Management Practices

Pier 3 Project Upgrade



- Primavera Construction Management software
- Weekly meetings with contractor, tenant, engineer, and all stakeholders
- Construction inspection by Port of Tacoma
- Detailed 3-week look ahead
- Upgraded change order procedure



Sustainability

Pier 3 Project Upgrade



- Remodeling far more cost effective than rebuilding
- Used purple epoxy-coated reinforced steel

- Reuse of the pier ballast
- Spare conduits installed for future-use scenarios
- All exposed galvanized steel was painted



Safety

Pier 3 Project Upgrade

- No lost time incidents
- 53,000 hours of craft labor on job site
- Special signage to guide construction traffic through active container yard



- Close coordination with intermodal operations tower to accommodate construction traffic

Environmental Considerations

Pier 3 Project Upgrade



- Pile driving during the fish window (February 15 to July 15)
- Concrete pumped on the outgoing tide
- Soil testing at multiple locations to ensure proper disposal of contaminants
- Accelerated crane beam construction to minimize disruption to fish

Community Relations

Pier 3 Project Upgrade



- Weekly pile driving updates to the Northeast Tacoma Community Association
- Regular communication with longshore ensured that construction continued alongside the railroads, trucks, and straddle carriers
- Weekly communication with Husky ITS, tenant



Unusual Accomplishments

Pier 3 Project Upgrade




- Structural work extremely tide dependent, low tides generally in the middle of the night
- Construction footprint minimized to reduce impact to terminal
- Pile collars and false work in the intertidal zone

Conclusion

Pier 3 Project Upgrade



- Success of project
- Collaborative effort from top down
- On time
- On budget
- Accepted Westwood Shipping Lines 2 weeks after completion
- Best bang for the buck!



Thank you!

