AAPA Facilities Engineering Seminar & Expo October 19-21, 2015 San Diego, CA

#### Pier 3 Upgrade Project

Thais Howard, PE, MASCE Director, Engineering Port of Tacoma



#### Future Facility Plan Pier 3 Project Upgrade



Project Team Members	
Owner:	Port of Tacoma
Port Project Manager:	Stanley Ryter, PE, PMP
Engineer of Record:	BergerABAM
Electrical Engineer:	Cross Engineering
General and Marine Contractor:	Orion Marine Group
Electrical Subcontractor:	REP
Earthwork Subcontractor:	Roadway Construction
Construction Cost:	\$15M
Total Project Cost:	\$20M





# Future Facility Plan Pier 3 Project Upgrade



- Redevelop the General Central Peninsula
- Realign Pier 4 with Pier 3
- Simultaneously operate up to ten 100'-gauge container cranes
- Berth 2 ultra large container ships



# Design Vessel Requirements Pier 3 Project Upgrade



- Vessels between 5,000-18,000
   TEUs (twenty-foot equivalent units)
- Maximum anticipated draft of 50'
- Vessel width up to 23 containers





# Project Overview Pier 3 Project Upgrade





- All new appurtances
- Electrical distribution capacity upgrade

- Step 1 in the long-term plan
- Strengthening of pier for increased loads



## Constructed Project Elements Pier 3 Project Upgrade



- 100 precast pre-stressed piles
- Replacement of waterside crane beam
- Upgrade of the fender system
- Upgrade of bollards





#### Constructed Project Elements (cont) Pier 3 Project Upgrade

Tacoma

 Strengthening of landside crane beam and installation of 100'gauge crane rail





- Additional 36 concrete piles on landside crane beam
- New electrical substation for 13.8kV power

# Constructed Project Elements (cont) Pier 3 Project Upgrade





New bollards



New crane rail

# Constructed Project Elements (cont) Pier 3 Project Upgrade



- Infrastructure for future cold ironing
- Relocation of existing light poles
- Demolition of existing 5kV electrical substation






 Maintenance of service for 4 existing 64'-gauge cranes

#### Schedule and Budget Pier 3 Project Upgrade



- Substantial completion October 27, 2014
- 460 calendar days construction
- On budget with total project cost of \$20M



# Management Practices Pier 3 Project Upgrade



- Primavera Construction
   Management software
- Weekly meetings with contractor, tenant, engineer, and all stakeholders
- Construction inspection by Port of Tacoma
- Detailed 3-week look ahead
- Upgraded change order procedure



# **Sustainability Pier 3 Project Upgrade**





- Reuse of the pier ballast
- Spare conduits installed for future-use scenarios
- All exposed galvanized steel was painted

- Remodeling far more cost effective than rebuilding
- Used purple epoxy-coated reinforced steel



# Safety Pier 3 Project Upgrade



- No lost time incidents
- 53,000 hours of craft labor on job site
- Special signage to guide construction traffic through active container yard





Close coordination with intermodal operations tower to accommodate construction traffic

#### **Environmental Considerations Pier 3 Project Upgrade**





- Pile driving during the fish window (February 15 to July 15)
- Concrete pumped on the outgoing tide
- Soil testing at multiple locations to ensure proper disposal of contaminants
- Accelerated crane beam construction to minimize disruption to fish

# **Community Relations Pier 3 Project Upgrade**



- Weekly pile driving updates to the Northeast Tacoma
   Community Association
- Regular communication with longshore ensured that construction continued alongside the railroads, trucks, and straddle carriers
- Weekly communication with Husky ITS, tenant



# Unusual Accomplishments Pier 3 Project Upgrade





- Structural work extremely tide dependent, low tides generally in the middle of the night
- Construction footprint
   minimized to reduce impact to
   terminal
- Pile collars and false work in the intertidal zone

# **Conclusion Pier 3 Project Upgrade**



- Success of project
- Collaborative effort from top down
- On time
- On budget
- Accepted Westwood Shipping
   Lines 2 weeks after completion
- Best bang for the buck!



