







## Bayonne Bridge Historical Context

- Designed by Othmar Ammann and Cass Gilbert
   Also designed The George Washington Bridge; Triborough Bridge;
   Bronx Whitestone; Throgs Neck; and Verrazano-Narrows
- Opened to traffic on November 15, 1931
   1675 foot, steel arch span was the longest in the world at the time, and remained so for 46 years



2001 National and NJ State Historic Register Eligible (2003 NY Eligible)






GACY OF OTHMAR H. AMMANI






### The Bayonne Bridge Navigational Clearance

What's the ????










### The Bayonne Bridge Video






# Problem: Bayonne Bridge Air Draft Restriction

- Existing 151-foot air draft
- The expansion of the Panama Canal will allow for newer, larger, (Post-Panamax) ships with increased clearance requirements
- Taller ships (up to 200-ft), will not be able to navigate beneath the Bayonne Bridge
- The Bridge of the Americas (Pacific approach to Panama Canal), has a 201 foot clearance
- Trends in Shipping (shown in photo)
  - 8,000 TEU Regina Maersk
  - 13,000 TEU Emma Maersk







#### The Port of New York and New Jersey

Busiest port on the Eastern Seaboard - 30% of shipping traffic

Third largest container port in the Western Hemisphere, and 27th largest in the world

\$202. 6 Billion in cargo came through the port in 2013. Almost 80% of imports support commerce in the surrounding region

#### Port activity supports:

- · 280,000 jobs
- \$11.2 Billion in annual personal income

Kill Van Kull provides maritime access to Port Newark-Elizabeth and Howland Hook Marine Terminal in Staten Island, NY

**Economic Impact of Bayonne Bridge Construction Program** 

- 6,300 Total Job years (or approximately 1500 jobs/year)
- \$ 380 Million in Wages
- \$1.6 Billion in Regional Economic Activity



#### **Program Benefits**





- Enhance regional economic competiveness
- The Bayonne Bridge Project will generate more than 2,500 construction jobs, \$380 Million in wages, and more than \$1.6B in regional economic activity
- Increase environmental sustainability, access for newer larger ships
- Modernize the roadway with wider 12-foot lanes, median divider, and shoulders
- Maintenance of community character No ROW required
- Wider, full length Pedestrian Walkway / Bikeway
- Potential for future Transit Access



### Alternatives Review and Analysis

#### **BRIDGE MODIFICATIONS**


- Raise the Roadway (Retrofit or New Piers)
  - Jack the Arch
  - Lift Bridge

#### **BRIDGE REPLACEMENT**

- New Bridge
- New Tunnel

#### **NON- BRIDGE ALTERNATIVES**

- Ferry Service (Vehicular/Passenger)
- Lock System (Kill Van Kull)



Staten Island Advance, Monday, August 24, 2009









# Bayonne Bridge Alternatives Review and Analysis

Alternative	Bridge Modification			Bridge Replacement		Non-Bridge		
Criteria	Raise the Roadway	Jack Arch	Lift Bridge	New Bridge	New Tunnel	Alternate Port Sites	Lock	Ferry
Constraints/ Operational Limitations	<b>√</b>	*	*	<b>√</b>	<b>√</b>	*	×	*
Neighborhood / Environmental Impacts	<b>√</b>	<b>√</b>	*	*	*	*	×	*
Cost	<b>√</b>	×	$\checkmark$	*	×	*	-	-
Schedule	<b>√</b>	×	*	*	×	*	×	-

## "Raise the Roadway "Bayonne Bridge Rehabilitation and Retrofit





**Existing** 


- 151 ft. air draft
- 6 ft. walkway
- 4-10 ft. lanes, no shoulders
- No median barrier

#### **Proposed**


- √ 215 ft. air draft
- √ 12 ft. walk / bikeway
- √ 4-12 ft. lanes, with shoulders
- ✓ Median Barrier and additional width for future transit



# Existing/ Proposed Roadway Design - Within Arch




#### EXISTING ROADWAY (4 - 10 FOOT LANES, NO SHOULDERS, 6 FOOT WALKWAY)



PROPOSED ROADWAY (4 - 12 FOOT LANES, PARTIAL SHOULDERS, 12 FOOT WALKWAY/BIKEWAY)







## Bayonne Bridge Interagency Coordination and Regulatory Review Process

### Approximately 50 permits from 20 different Agencies

#### **Federal**

- US Army Corp of Engineers
- US Coast Guard
- US Fish and Wildlife Service
- Marine Fisheries Service
- Amer Council on Historic Preservation
- US Environmental Protection Agency (EPA)

#### **State of New York**

- NYS Dept of Environmental Conservation
- NYS Dept of State
- NYS Dept of Transportation
- State Historic Preservation Officer (SHPO)
- Utility Relocation / Coordination

#### **State of New Jersey**

- NJ Dept of Environmental Protection
- NJ Dept of Transportation
- State Historic Preservation Officer
- Utility Coordination


#### **Local / Municipal**

- · City of Bayonne
- County of Hudson
- Hudson County Sheriff's Office
- NY / NJ Elected Officials
- NYC Dept of Environmental Protection
- NYC DOB
- NYC Dept of Transportation
- NYC Transit Authority





# **Bayonne Bridge Schedule - Expedited Program Schedule**




# Pro

### **Program Timeline**

- March 2008 US Army Corps of Engineers initiates National Cost Benefit Analysis (Federal Funding Potential)
- August 2009 PA Initiates Conceptual Planning and Engineering
- December 2010 PA selects "Raise the Roadway" Alternative
- Nov 2011 Complete Preliminary Engineering Design (Joint Venture HDR/PB)
- August 2011 NEPA Environmental Review Initiated (USCG Lead Fed'l Agency)
- April 2012 Contractor Pre Qualification (RTQ) Solicitation Outreach Meeting
- July 2012 Announce Pre Qualified Construction Contractor Teams
- December 2012 Complete Final Engineering Design
- Q2 2013 Complete Environmental Review and Permits
- Q2 2013 Award Bayonne Construction Contract: Skanska-Koch Kiewit, JV
- 2017 Interim Milestone: Navigational Clearance
- 2019 Complete Construction



#### **Construction Work Zone Overview**





# Environmental, Regulatory, and Community Issues - Overview

#### **Traffic - Roadway Closures - Parking**

#### Noise \*

Compliance with Noise Code (day; night; weekend limits)

#### Air Quality \*

- 3 Tiered Dust / Air Monitoring Program (1) Regional Air Quality,
- (2) Areas with Known Contaminants (Lead/Arsenic), (3) Perimeter Dust Trackers
- Real Time Investigation and Incident Reports

#### **Community Assistance Program**

- Window Replacement Program
- Temporary Hotel Program

#### NY / NJ Outreach Office / 800 Hot Line

\* Air and noise monitoring exceeds all Federal requirements







# BBNCP Comprehensive Community Assistance Program (CCAP)

- Air, Dust, and Soil Monitoring and Testing
- Noise Monitoring
- Pre-Construction Condition Surveys
- Window Replacement Program (Approximately 30% residences complete)
- Temporary Hotel Stay Program
- Local Street Cleaning Services
- Summer Shuttle Service
- Misc (Power Washing, Extermination Services, Pool Cleaning, Pool Covers, Car Wash Vouchers, Landscaping Repairs, etc.)
- Air Conditioner Reimbursement Program
- Community Mitigation Program Management and Audit Services
- Traffic and Air Quality Monitoring and Mitigation Program

**City of Bayonne Reimbursement Agreement Staten Island Reimbursement Agreement** 



#### **Animation**



#### Proposed Deck Removal By Barge

- Minimizes community impacts, versus segmented roadway removal by truck
- Saves time.
- Partial channel closure successfully utilized in prior projects
- Assume partial channel closures: North, Center, and South
- Each closure period is 6-8 hours long and up to two deck segments can be removed during each closure
- Removal of all 12 deck segments will require a total of 8 closure periods, each 6 -8 hours in length
- Flexibility for nonconsecutive, off-peak, or midday closures

**Navigational Clearance Obtained: 2017** 





### **Bayonne Bridge Construction Activities**

#### **Construction Staging**

- Bridge remains open during construction
- Shift four lanes of traffic into two lanes (west side)
- Construct two (2) travel lanes on the east side at the higher 215-foot elevation
- Remove existing 151-foot roadway deck
- Continue construction and complete bridge (2018)

#### View from top of Arch

- Northbound, Two-Lane, Roadway Deck Removed (East Side)
- Steel Safety scaffolding Exposed Under former Northbound Roadway
- Two Vehicular Travel lanes (one northbound and one southbound), shown on






# Construction Activities – Main Span – Arch Lightening













### Construction Activities – Main Span – NY Tower and Portal





# Construction Activities – Main Span – NY Lower Chord and Node Strengthening






# Construction Activities – Main Span – NY Lower Chord Strengthening






# Construction Activities – Main Span – New Steel Framing




Construction Activities – Main Span –

**New Steel Framing** 





### BBNCP: Construction Activities – New Steel Tower NJ Side





## Construction Activities – Approaches – Selective Demolition













### Construction Activities – Approaches - Drilled Shafts












# Construction Activities – Approaches - Foundations














# Construction Activities – Approaches - Precast Concrete Pier Segments











## Construction Activities – Approaches –Pier Erection





# Construction Activities – Approaches - Precast Concrete Roadway Segments












# Construction Activities – NY Tower






# Construction Activities – NY Approach Structure Launching Gantry






### Construction Activities – NJ Approach Structure Pier Erection






### Construction Activities – NY Approach Structure Pier Erection





### Construction Activities – Main Span Arch





# Bayonne Bridge "Raise the Roadway" Gantry Operation Time Lapse





# Bayonne Bridge "Raise the Roadway" Gantry Operation Time Lapse






### Bayonne Bridge Summary


- 40 % overall construction complete
- Northbound Roadway
  - Drilled Shafts 100% complete
  - Sheeting 100% complete
  - Foundations 100% complete
  - Pier Segments Cast 100% Complete
  - Pier Columns 12 of 24 complete
  - Steel Towers 100% Complete
  - NY & NJ Abutments 95% complete
  - Precast segment NY & NJ launching gantries complete and operational
  - Roadway segments cast 94% Complete
  - · Roadway segments Installed
    - NY 18%
    - NJ 32%







#### **Program Website**



### www.panynj.gov/bayonnebridge

Sign up for E-Alerts for Up to Date Travel Information



### **Questions?**

