

## Terminal Master Planning: A Key Planning Process Before Design Begins

Present At

AAPA Marine Terminal Management Training Program September 15, 2015







- > Founded in 1945
- A strong reputation throughout our domestic and international operations
- > Engineering News Records Top Firms Lists
  - > #23 Top 500 Design Firms
  - > #32 Top 200 Environmental Firms
- > A Dedicated staff that specializes in port/terminal planning and design:
  - > Port and Terminal Master Plans
  - Bulk Terminal Planning and Material Handling Studies and Design
  - > Container Terminal Designs
  - > Equipment Studies and Specifications
  - > Cost Estimating
  - > Vessel Maneuvering and Hydrodynamic Modeling
  - Dredged Material Management and Navigational Studies
  - > Sustainability and Energy Planning





## Terminal Master Planning Is An Important Step in The Design Process

- Terminal Master Planning or "Program Planning" is <u>Not</u> the same as preliminary design;
- > Master Planning is more the "programmatic" phase of a project
- Master Planning a terminal before design starts will allow the Owner to:
  - > Identifying problems and solutions early in the process
  - > Determine project requirements
  - > Finalize the design program and schedule;



#### An Example Of Program Planning - Port of Houston Barbours Cut Terminal (BCT) Improvements

#### Project Team: DANNENBAUM

 Prime Program Management Consultant



- Lead Terminal Planners
   Halcrow
- (now CH2MHIII)- Wharf
   Concepts
   CargoVelocity
- Automation Concepts

#### **Project Owner:** Port of Houston Authority



#### Existing Barbours Cut Terminal (BCT) Attributes

- > 175 Acre Terminal
- > 5,000 LF Wharf / 5 Berths (PHA only)

(A 6th Berth was operated by APMT, but now back to POHA)

- Existing STS Cranes 50' Gage
- > CY a combination of RTGs and wheeled storage
- > Empties stored offsite





## Landside Interface - Existing Condition - 50 Gage



#### > Amenities Building mixed in A-Row



#### Port of Houston Authority (PHA) Stated Operational Goals For The Program

- > Retrofit wharf for 100-gage Quay Cranes (22-Wide) – Can not change existing berth-line!
- > Construct minimum 1,000 FT of new wharf by 2014
- > Densify yard to handle + 2.0 million TEU/yr
  - > RTGs
  - > RMGs
  - > Automated system
- > Return empty depot operations to on-site within BCT



## Wharf Operations Studies Early In the Program

> Berthing Concept Study >Berth Capacity Model Results >Wharf Face Operation Study Crane Rail Position Study >Impact of 100 Gage Crane on Yard >Amenities Building Location Study



### **Berth Capacity**

- >Berth capacity model set up to assess multiple berth segments and number of cranes per berth
- Some enhancements were considered to improve productivity in the future
- >Evaluate unit berth capacity under various crane options and apply to the number of berths available



## Berth Capacity Based on Crane and Berth Count

BCT Berth Capacity (future crane count)	2.0	2.5	3.0	3.5	4.0
Berth Capacity - 4 Berths (Lifts/year)	993,651	1,213,242	1,422,874	1,623,208	1,814,850
Per Berth Capacity - 4 Berths (TEUs/year)	1,649,460	2,013,982	2,361,970	2,694,525	3,012,651
Total Cranes - 4 Berths	8	10	12	14	16
Berth Capacity - 5 Berths (Lifts/year)	1,242,064	1,516,553	1,778,592	2,029,010	2,268,562
Per Berth Capacity - 5 Berths (TEUs/year)	2,061,825	2,517,477	2,952,463	3,368,156	3,765,813
Total Cranes - 5 Berths	10	13	15	18	20
Berth Capacity - 6 Berths (Lifts/year)	1,490,476	1,819,863	2,134,310	2,434,812	2,722,275
Per Berth Capacity - 6 Berths (TEUs/year)	2,474,191	3,020,973	3,542,955	4,041,788	4,518,976
Total Cranes - 6 Berths	12	15	18	21	24

- > 4 Berths adequate for 2 million TEU range
- > 5 Berth scenario for 3 million TEU range
- > Some flexibility in crane count / berth
- > Yard capacity will drive berth demand



## Berth Face Operations Study – Key to setting W/S Rail Location

- Existing berth-line/wharf face location needed to be maintained
- > Need to determine future wharf face activities
  - > Crane power system
  - > Accommodation ladders
  - > Bollards
  - > Future cold iron vaults
  - > Service truck access





## Berth Face Operations Study –Studied Various Options





## Fill vs No-Fill Alternatives Adds a 6<sup>th</sup> Berth



## Fill vs. No-Fill Capacity Analysis (TEUs)

RTG Layout	Yard Capacity	Berth Capacity	Limiting Factor		
No Fill	3,293,202	2,619,696	Berth		
Fill	3,445,387	3,274,620	Berth		

- > "No Fill" option 4 berths
- > "Fill" option 5 berths
- > Assumes 4 cranes/berth
- > Some additional capacity by adding cranes
- > Roughly +150,000 TEU/yr gained by adding fill and 5<sup>th</sup> berth
- It was determined that the Project Goals could be met with the No-Fill Option and the area behind the "fill section" could be better used for storage of break-bulk/project cargo.



## Landside Interface : Existing Layout - 100 Gage



Retain existing RTG pad layout
Impacts A-Row & Amenities Building
101' from LS crane rail to B-Row



## Landside Interface – Options RTGs Back to Back - 100 Gage



- > Back to Back layout
- > 121 ' from LS crane rail to B-Row



#### Landside Interface - Final



- > Width/Requirements of Amenity Strip
- > RTG Pad location and operation (One Way or Back-to-Back)
- > RTG Pad distance from L/S Rail
- > Width of Passing Lanes
- > Light Pole and Camera Locations



#### Narrow Amenities Strip



- Separate buildings from RTG pad
- 134 FT wharf apron
- 40 FT amenities strip
- Allows area for:
  - Substations
  - Electrical Equip
  - Misc Truck/equip. parking
  - Boneyard



### Yard Layout Alternatives

- > Three alternatives considered:
  - > RTG Dense operations
  - > ASC Perpendicular to the wharf
  - > ASC Parallel to the wharf
- > General layouts provided for discussion
- > Blocks provided for major terminal elements
- > Further detailed layouts required



### Camera Pole Study Goals

- > Place camera pole at each RTG pad to view operations
- > Avoid conflicts with yard circulation and RTGs
- > Minimize impacts on terminal footprint
- Investigate using 80 FT high pole at each bypass lane for cameras
- Investigate placing wireless cameras on RTG's



## <sup>'</sup>E-RTG Concept Study Evaluated Cost and Capacity of E-RTGs vs. Diesel RTGs

#### > Benefits:

- > 30% lower maintenance costs
- > 80% lower fuel costs
- > 60 80 % emissions reduction

#### > Constraints:

- > Fixed runway positions
- > Increased civil costs for power delivery and substations



#### E-RTG Concepts, cont.



# > Power Delivery Methods > Motorized cable reel > Conductor bar





#### Projected Return on Investment

- > Estimated Capital Costs \$33,503,433
  > Operating Cost Savings \$2,923,000/yr
- > Projected Capital Cost Recovery +11 years
- > POHA decided to stay with Diesel RTGs because of similarities with other PHA Terminals (Bayport)



#### PHA Yard Layout Wish List

- > Maximize RTG storage area
- > Approx 50 acres for empty containers
- > Approx 50 Ag Ramp slots
- > 100 to 300 wheeled slots
- > Wheeled reefer slots initially
- > Dedicated area for VACIS inspections



#### Further Plan Refinement, cont.

#### > Modify CY terminal aisles to increase velocity

- > 20 FT truck bypass lanes
- > Dedicated RTG shuttle lane on entry gate aisle (114 FT)
- > N-S Aisles at 80 FT
- > Intra-terminal 4-lane road at 60 FT



#### Final Terminal Layout



## Summary of Final RTG Composite Plan

#### > TGS Count

- > RTG Loads 11,664
- > Reefer Racks 108
- > Empties 7,346
- > Wheeled Reefers 118
- > Misc Wheeled 249
- > Empty container storage> Ag Ramp slots

+32 acres 50 slots



## Automated Staking Crane (ASC) Alternative

- > An Option For Future ASC Operation Was Studied;
- > Would allow for the future conversion of the CY to ASC
- > Buildings and other facilities were located so as to not be impacted by a future conversion
- > A Phasing Plan was developed so the terminal could be converted to ASC by phases



### ASC Composite Plan



## PHA Phasing Plan Preferences

- > Focus redevelopment on wheeled areas first
- Maximize development of break bulk terminal
- > Accelerate relocation of empty handling op's to BCT
- > Redevelop waterfront RTG pads last
- > Prefer working minimum three pads adjacent with same aisle alignment



## **RTG Phasing Plan**



## **RTG Phasing Plan**









## Near Term Construction Phasing Project 1 - Phase 1 (June 2013)

#### Terminal C5 yard construction (11.7 AC)

Phase addition: + 936 TGS

Phase removal: -720 TGS

Phase Net: + 216 TGS

Cumulative through project: +216 TGS





AAPA Marine Terminal Mana 2015

## **Near Term Construction Phasing** Project 1 - Phase 2 (April 2014)

**Terminal C5 operational** during Rehab Wharf 1 No change in TGS count (Still +216 TGS)

2015



## **Near Term Construction Phasing** Project 2 - Phase 1 (June 2014)

Phase addition: + 984 TGS Phase removal: -102 TGS Phase net: + 882 TGS Cumulative: +1098 TGS

2015



## **Near Term Construction Phasing** Project 2 - Phase 2 (October 2015)



2015



## Near Term Construction Phasing Project 4 - Phase 1 (5-7 Year Plan)

Project addition: + 1056 TGS Project removal: -264 TGS Net: + 792 TGS Cumulative through project: + 3546 TGS



## Near Term Construction Phasing Project 5 - Phase 1 (6-10 Year Plan)

Phase addition: + 2952 TGS Phase removal: - 2454 TGS Phase net: + 498 TGS Cumulative through project: + 4044 TGS

INTRATERMINAL ROAD



## Near-Term Phasing Project Timeline

## **Near-Term Construction Phasing**

- > Project 1 Rehab Wharf 1 and C-5 Yard (0-3 Year Plan)
- > Project 2 Rehab Wharf 2 and C-4 Yard (0-4 Year Plan)
- > Project 3 Break Bulk Area (3-6 Year Plan)
- > Project 4 C-3 Yard (5-7 Year Plan)
- > Project 5 C-1/C-3 Waterfront (6-10 Year Plan)

			Year										
Project	Phase	Description	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022
1	1	C-5 South Yard											
1	2	Rehab Wharf 1											
2	1	C-4 South Yard											
2	2	Rehab Wharf 2											
2	3	Substation & 12 kV Distribution											
3	1	Breakbulk Area											
4	1	C-3 South Yard & C-5 Backland											
5	1	C-1 to C-3 Waterfront											



## Near Term Construction Phasing TGS Count by Project

Projects	Project 1	Project 2	Project 3	Project 4	Project 5	Cumulative
TGS Constructed	936	984	1656	1056	2952	7584
TGS Removed	-720	-102	0	-264	-2454	-3540
Project Net	216	882	1656	792	498	4044
Project Cumulative Gain	216	1098	2754	3546	4044	

- > Each project adds more TGS than it removes
- After project is completed, the CY will have 4,044 more TGS than when construction began

AAPA Marine Terminal Management Traini 2015



## Another Critical Item Is Laydown Areas and Haul Routes During Construction



## Wharf 1 Project Completed Fall 2014 Wharf 2 Advertised For Bid Fall 2015



- Berth 1 Completed;
- 4 New Post-Panama Cranes Delivered;
- Terminal areas 4 & 5
   improvements
   completed
- Berth 2 project currently out for bid



### Conclusion

- Program Planning (Master Planning) is a critical element to any terminal development project;
- > There are many "small" items that have to be considered during this planning process;
- > Successful Program Master Planning ensures successful design and construction programs.
- > For More Information:
  - Jim Hunt Principal Port Planner Email: james.hunt@cardno-gs.com

